1 REVISED

RUMBLE STRIPS

LOG MILE	LOG MILE	LOCATION	EXCEPTIONS FT	SHOULDER RUMBLE STRIP STA	REMARKS
66.203	80.956	LT/RT OF ℄ NBL	538.00	1547.16	EXCEPTIONS BR# A0938, A0913
129.052	143.650	LT/RT OF ℄ SBL	538.00	1530.79	EXCEPTIONS BR# A0938, A0913
			TOTAL	3078.0	

LOG MILES ARE APPROXIMATE. EXACT LOCATIONS TO BE DETERMINED BY ENGINEER

STEEL BAR DAM

LOG MILE	LOCATION	STEEL BAR DAM EACH	REMARKS
75.416	NBL	1.0	A0913
134.356	SBL	1.0	A0913
	TOTAL	2	

LOG MILES ARE APPROXIMATE. EXACT LOCATIONS TO BE DETERMINED BY ENGINEER

GUARDRAIL

LOG MILE	LOCATION	MGS BRIDGE APPROACH TRANSITION SECTION EA	MGS GUARDRAIL LF	MASH CRASHWORTHY END TERMINAL EA	MGS END ANCHOR EA	MODIFIED SHAPING SLOPES CLASS III LF	REMARKS
67.367	RT OF ℄ NBL		425.0	1	1	80.0	I-55
67.474	RT OF ℄ NBL	2	1587.5	1	1	80.0	A0938
67.474	LT OF ℄ NBL	1	25.0	1		80.0	A0938
69.379	LT OF ℄ NBL		262.5	1	1	80.0	ROUTE HH BULLNOSE
71.906	LT OF ℄ NBL		262.5	1	1	80.0	ROUTE H BULLNOSE
71.906	RT OF ℄ NBL	2	275.0	1	1	80.0	ROUTE H OVERPASS
74.566	RT OF ℄ NBL	2		1	1	80.0	BOX CULVERT
75.416	RT OF ℄ NBL	2	2525.0	1	1	730.0	A0913✳
75.416	LT OF ℄ NBL	1	387.5	1		80.0	ADDED A0913
77.554	RT OF ℄ NBL		75.0	1	1	80.0	MESSAGE BOARD
77.618	LT OF ℄ NBL		262.5	1	1	80.0	ROUTE C BULLNOSE
77.618	RT OF ℄ NBL	2	137.5	1	1	80.0	ROUTE C OVERPASS
80.781	RT OF ℄ NBL		662.5	1	1	80.0	MO 77 OFF RAMP RIGHT SIDE
80.781	RT OF ℄ NBL	1	512.5	1		80.0	MO 77 OFF RAMP LEFT SIDE
132.225	LT OF ℄ SBL		262.5	1	1	80.0	ROUTE C BULLNOSE
132.225	RT OF ℄ SBL	2	150.0	1	1	80.0	ROUTE C OVERPASS
134.356	RT OF ℄ SBL	2	2525.0	1	1	700.0	A0913✳
134.356	LT OF ℄ SBL	1	25.0	1		80.0	ADDED A0913
135.266	RT OF ℄ SBL	2		1	1	80.0	BOX CULVERT
137.950	LT OF ℄ SBL		262.5	1	1	80.0	ROUTE H BULLNOSE
137.950	RT OF ℄ SBL	2	262.5	1	1	80.0	ROUTE H OVERPASS
138.880	RT OF ℄ SBL	2		1	1	80.0	BOX CULVERT
140.465	LT OF ℄ SBL		262.5	1	1	80.0	ROUTE HH BULLNOSE
142.329	RT OF ℄ SBL	2	1625.0	1	1	80.0	A0938
142.329	LT OF ℄ SBL	1	25.0	1		80.0	A0938
142.416	RT OF ℄ SBL		250.0	1	1	80.0	US 62 OFF RAMP
142.474	RT OF ℄ SBL		500.0	1	1	80.0	I-55
143.295	LT/RT OF ℄ SBL	4		2	2	160.0	TRUSS SIGN
	TOTAL	31	13550	29	24	1430	

1 ADDED

810.0 1

780.0 1

3750 1

✳GUARDRAIL LENGTH TO BE EXTENDED TO ROCK LET DOWN AND ASPHALT CURB TO BE REMOVED
PLACE NEW GUARDRAIL IN THE SAME LOCATION OF EXISTING GUARDRAIL
GUARDRAIL FLARE RATE IS 24:1
LOG MILES ARE APPROXIMATE. EXACT LOCATIONS TO BE DETERMINED BY ENGINEER

STATE OF MISSOURI
TIMOTHY CHRISTOPHER PICKETT
NUMBER PE-2017000351
PROFESSIONAL ENGINEER

THIS SHEET HAS BEEN SIGNED, SEALED AND DATED ELECTRONICALLY.

DATE PREPARED 10/5/2020

ROUTE	STATE
I-55	MO
DISTRICT	SHEET NO.
SE	3

COUNTY SCOTT

JOB NO. J9I3545

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

SUMMARY OF QUANTITIES
SHEET 5 OF 6